

GC-2 Spill Site Snow Melt Plan

Two (2) snow melters will be set up on the ice pad outside of CC2A pit. Snow melters will be placed inside secondary containment and operated/monitored by two (2) personnel 24 hours a day. Materials will be fed to the snow melters from the adjacent pad CC2A pit with a small loader. If more snow is removed from spill site for delivery to CC2A pit, ice pad and access ramp to pit will be cleaned prior to delivery. Intermittent loads will no longer be hauled to CC2A. Additional snow will be accumulated at the spill site and hauled in bulk to minimize operational impacts. Melted fluids will be manifested for disposal by BP Environmental personnel per waste disposal plan.